

VISAKHAPATNAM PORT TRUST  
MECHANICAL & ELECTRICAL ENGINEERING DEPARTMENT

Sub: Renovation of Bungalow No.8 at Harbour Park – Reg.

Last Date & Time of Receipt of Tenders in CME's Office AT 14.30 HOURS ON 09.12.2015

ESTIMATE

S.NO	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Supply , fixing connecting and commissioning of recess mounting type, 6 to 9 W LED down lighter fitting to the existing false ceiling duly making suitable hole, fixing the fitting etc. similar to the model no FLDLR -02-09 CW or MW of M/s Holonex as directed by engineer in charge including all labour tools and tackles	26	Nos.		
2	Supply fixing and connecting of following premium quality modular type ivory colour switches conforming to IS3854:97 guaranteed for 5 years/4000 operations on the existing top plates as directed by Engineer I/c including all material labour tools and tackles.				
	Switch 5/6 amps, one way	122	Nos.		
	Switch 5/6 amps , 2 way	12	Nos.		
	Switch 15/16 amps	14	Nos.		
3	Supply fixing and connecting of following premium quality modular type ivory colour supply sockets conforming to IS1293:88 guaranteed for 5 years/4000 operations on the existing top plates as directed by Engineer I/c including all material labour tools & tackles.				
	Socket 5/6 amps	30	Nos		
	Socket 15/16 amps	21	Nos		
4	Supply fixing and connecting of following premium quality modular type ivory colour step type ceiling fan regulators on the existing top plates suitable for a load of 120W (max) guaranteed for 5 years on the existing top plates as directed by Engineer I/c including all material labour tools and tackles.	10	Nos		

5	Supply and fixing of Dummy plates matching to the existing switches to close the gaps on the existing modular plates as directed by Engineer I/c including all material labour tools and tackles`	30	Nos		
6	Supply and fixing of following premium quality modular type ivory colour top plates for fixing of switches/ sockets/regulators etc. as directed by Engineer I/c including all material labour tools and tackles				
	Covering plates 16/12 module	14	Nos		
	Covering plate 8 module	3	Nos		
	Covering plate 6 module	10	Nos		
	Covering plate 4 module	3	Nos		
	Covering plate 3 module	10	Nos		
	Covering plate 2 module	2	Nos		
	Covering plate 1 module	1	Nos		
7	Supply fixing and connecting of following modular type boxes duly flushed in the wall conforming to IS 3854 :1997 as directed by engineer –in-charge including all material labour tools and tackles.				
	Flush type boxes 12-16 module	14	Nos		
	Flush type boxes 6-8module	13	Nos		
	Flush type boxes 4-5 module	3	nos		
	Flush type boxes 1-3 module	13	nos		
8	Supply, fixing connecting and commissioning premium quality modular type Starter of 25 amps rating suitable for control of AC unit (up to 2 TR capacity ) on the existing box as directed by engineer –in-charge including all material labour tools and tackles.	6	nos		

Note: The Estimate cost is Rs.1,42,700/-

### Criteria

1.The firm has to pay E.M.D Rs.2,855- in the form of Bankers' Cheque / Pay Order / Demand Draft of Nationalized Banks drawn in favour of F.A & C.A.O., VPT.

2.The firm has to pay cost of Tender Documents Rs.200/- in the form of B C / P O / D.D of any Nationalized Banks drawn in favour of F.A & C.A.O.

(The firms, who are not complying with any one of the above criteria, their tender will be summarily rejected)

### Terms and conditions:

1. The Contractor has to submit the offer duly super-scribing the name of the work on the envelope.
2. Firm's quoted rate shall be inclusive of all taxes & duties but excluding Service Tax.
3. Validity of offer should be two months from the last date of receipt of the offers.
4. Statutory deductions will be made from the bills.
5. Conditional offers will be rejected.
6. In case of any clarification, Please contact at phone No. 2873207/2873193.
7. The workmanship and materials used in this work shall be guaranteed for a period of 12 months from the date of completion of the work.
8. The work should be completed within 21 days from the date of lifting the material/ Site clearance. The time for completion of the work is the essence of the Contract.
9. The work shall be completed within the stipulated period, failing which a penalty @ ½% will be levied for every week of delay, on the part of the contractor subject to maximum 10% on total contract / executed value.
10. Firms who have not worked earlier in VPT they have to submit copy of the work experience in respect of similar completed works in other Government Organizations/PSUs/Ports etc towards proof of experience of similar works.

### Sealed Quotations are to be addressed to:

Executive Engineer (Elec)  
Mech & Electrical Engg.Dept.

Visakhapatnam Port Trust,  
VISA KHAPATNAM-530035

CONTRACTOR

Executive Engineer (Elec)