VISAKHAPATNAM PORT TRUST

MECHANICAL & ELECTRICAL ENGINEERING DEPARTMENT

Name of the work: Replacement of faulty 3.3 KV UG Cables&junction boxes at EQ-7 berth for 20 Ton capacity ELL Wharf cranes-Reg

Last date & time of Receipt of Tenders in C.M.E's office: 28.03.2016 at 14.00 Hrs.

WORK SCHEDULE

S.NO	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Supply and providing heat shrinkable HT straight through termination of approved brand suitable for 3 core, 3.3 KV (E), 120-185 sq.mm XLPE aluminum conductor cable complete with all labour, tools, tackles and materials. as directed by engineer in charge.Brands: Raychem/3M/Dension	1	Nos		
2	Supply and providing heat shrinkable HT indoor end termination of approved brand suitable for 3 core, 3.3 KV (E), 70-95 sq.mm XLPE aluminum conductor cable complete with all labour, tools, tackles and materials. as directed by engineer in charge. Brands: Raychem/3M/Dension	2	Nos		
3	Removal & Re-laying of RCC cover slabs on the road/cable trench without damage to the material as directed by engineer in charge including all labour tools & tackles.	12	Nos		
4	Laying of 3 core, 70-95 SQ. MM, 3.3KV (E) grade, armoured, XLPE insulated, PVC sheathed, stranded aluminium conductor cable in the existing trench complete with all labour, tools and tackles (cable will be supplied by VPT at free of cost.)	300	mts		
5	Cleaning of cable trench and removing the, debris cargo within a lead of 0.5 KM complete with all labour, tools, tackles and materials as directed by engineer in charge.	200	mts		
6	Supply, installation, testing and commissioning of 3.3 KV 400 amps FRP junction boxes consisting of 3 nos copper Bus bars with suitable epoxy resin insulators and supported with 50x50x6 mm FRP chanel and required earth studs at EQ-7 complete with all labour tools tackles and material as directed by engineer in charge.	2	Nos		
	TOTAL				

EXECUTIVE ENGINEER (Elec) I

Note:

The Estimate cost is Rs.1,68,677/-

Criteria:

1. **The firm has to pay E.M.D Rs.3,374/- in the form of Bankers' Cheque / pay order / Demand Draft of Nationalised Banks drawn in favour of F.A & C.A.O., VPT.**
2. **The firm has to pay cost of Tender Documents Rs.200/- in the form of B C / P O / D.D of any Nationalised Banks drawn in favour of F.A & C.A.O.**
3. **The firm has to submit the proof of experience in the similar field of work.**

(The firms who are not complying with any one of the above criteria, their tender will be summarily rejected)

Terms and conditions:

1. **The Contractor has to submit the offer duly super-scribing the name of the work on the envelope.**
2. **Firm's quoted rate shall be inclusive of all taxes & duties, except Service Tax.**
3. **Service Tax will be paid extra on submission of documentary evidence.**
4. **Validity of offer should be 2 month from the last date of receipt of the offers.**
5. **Statutory deductions will be made from the bills.**
6. **Conditional offers will be rejected.**
7. **In case of any clarification, Please contact at phone Nos: 2873193 / 2873207.**
8. **The workmanship and materials used in this work shall be guaranteed for a period of 12 months from the date of completion of the work.**
9. **The work should be completed within 30 days from the date of lifting the material / site clearance. The time for completion of the work is the essence of the contract.**
10. **The work shall be completed within the stipulated period, failing which a penalty @ ½% will be levied for every week of delay, on the part of the contractor subject to maximum 10% on total contract / executed value.**
11. **The tenderers can visit VPT Website www.vizagport.com to download tender documents.**

Sealed Quotations are to be addressed to:
Executive Engineer (Elec)
Mech & Electrical Engg.Dept.

Visakhapatnam Port Trust,
VISAKHAPATNAM-530035.

CONTRACTOR **EXECUTIVE ENGINEER(Elec)**