

VISAKHAPATNAM PORT TRUST  
MECHANICAL & ELECTRICAL ENGINEERING DEPARTMENT

Tender Notice No. IM&EE/MOF/MII/PWS/38/23, Dt.11-12-2015.

Sealed quotations are invited for the work of “Repairs / modification to the suction pipelines and replacement of delivery valves of 2 nos 25 HP pump sets at VPT pump house” as per the schedule of work furnished below.

**Last date & time of receipt is 21.12.2015 at 14.00 Hrs.in C.M.E’s Office**

**Tender opening on 21.12.2015 at 15.30 hrs.**

**Estimate put to tender: Rs. 91,200.00.**

**WORK SCHEDULE**

Sl No.	Description of Item	U/A	Qty	Rate	Amount
1)	Material and labour for removing the existing suction pipeline of 6” dia and extending the horizontal length of the suction by 1 meter by providing suitable 6” dia MS heavy grade pipeline similar to the existing one and fixing back the suction line in position with required flanges, fastners and gaskets including painting of the suction pipeline with two coats of marine grade anti-corrosive epoxy paint over a coat of primer complete as required and as directed by the Engineer-in-charge. NOTE: All the required materials, tools / tackles etc; are under the scope of the contract.	Job	02		
2)	Fabrication of steel for making supporting to the pipelines, ladder with platform / walkway along the suction pipeline upto the suction point in the pond of above pumps by using required angles, flats, channels, plate ,beams etc; including painting with two coat of marine grade anti-corrosive epoxy paint over a coat of primer and supply of required fastners complete as required and as directed by the Engineer- in-charge. NOTE: Required structural materials like angles, flats, channels, plates beams etc; will be supplied from VPT stores at PWS /STP at free of cost for installation.	MT	02		

Sl No.	Description of Item	U/A	Qty	Rate	Amount
3)	Materials and labour for replacement of deteriorated C.I 6" gate valves of 25 HP pumps at VPT pump house with new CI gate valve with brass gate of make Kirloskar/ Audco/ wag/ductile/ micron similar to the existing one with required gaskets, fastners including supporting/spacing flanges etc; complete as required and as directed by the Engineer-in-charge. NOTE: Old removed valves to be returned to PWS/STP stores.	No's	02		
				TOTAL	

Terms and conditions:

1. Transaction fee: All the participating bidders shall pay a transaction fee (non-refundable) for Rs.100/- D.D. in favour of FA&CAO/VPT from Nationalised / Scheduled Banks.
2. Firm's quoted rate shall be inclusive of all taxes & duties except service tax. Service tax will be reimbursed on submission of documentary proof.
3. Validity of offer should be 03 months from the date of receipt of the quotations.
4. The firm shall submit copies of executed work orders in Govt. / Private Firms to prove their experience in executing similar works in the last seven years. Similar works shall mean experience in "Pipe line installation or any kind of mechanical maintenance works in Pump houses / Pipe lines".
5. Statutory deductions will be made from the bills.
6. Conditional offers will be rejected.
7. In case of any clarification please contact phone No.0891-2873295/3213
8. The quotations received without complying with any of the above points is liable for rejection without assigning any reason.
9. The offer of the firm is liable for rejection in case of past poor performance record with VPT i.e. Quality, Delivery etc.,
10. Tender is to be submitted in a sealed cover duly super scribing the name of work and addressed to the Dy.M.M.(M), Visakhapatnam Port Trust, Visakhapatnam.
11. Work completion period should be 25 days from the date of site clearance.
12. In case work is delayed beyond reasonable time, VPT at its discretion will confiscate and the work will be executed at the cost, risks & responsibility of the contractor apart from initiating legal action as per the extant rules.

CONTRACTOR  
(Signature with seal)

Sealed Quotations are to be addressed to:  
DY.MATERIALS MANAGER (M)  
Mechanical & Electrical Engineering Department.  
VISAKHAPATNAM PORT TRUST,  
VISAKHAPATNAM -530035