

VISAKHAPATNAM PORT TRUST
MECHANICAL AND ELECTRICAL ENGINEERING DEPARTMENT
Name of the work: Dismantling, repairing, re-erection and commissioning of 30Mtrs.
High Mast lighting towers at Oil Wharf—reg.
Last date and time of receipt of tenders in C.M.E's Office at 15.00hours on
11-05-2016.

WORKSCHEDULE

Sl. No.	Description	Qty	Unit	Rate	Amount
1.	Dismantling of existing 30 mtrs High Mast towers from the RCC foundation duly lowering and removing the flood light fittings, lantern carriage with the assistance of suitable size / capacity crane as per the site requirement and other accessories as directed by the Engineer-in-charge with all labour, tools & tackle etc.	1	Job		
2.	Erection & commissioning of the above high mast lighting tower on the existing RCC foundation with the assistance of suitable size / capacity crane after attending fixing / repairing / replacement works with existing Wire ropes eye bolts, cables. Winch drum, light fittings, lantern carriage etc. with the assistance of suitable size and capacity crane and labour, tools, tackles etc. as directed by the Engineer –in-charge.	1	job		
3.	Supply of double drum 750 Kg.SWL gear box suitable for the above 30mtr. Lighting high mast tower along with base frame as directed by Engg.l/c including transportation loading and unloading etc.	01	No		
4.	Supply of SS 304 wire rope of size 6mm suitable for 30mtr. Lighting high mast tower as directed by Engg. l/c including transportation loading and unloading etc.	100	Mtrs		
5.	Supply of SS 304 wire rope of size 8mm suitable for 30mtr. Lighting high mast tower as directed by Engg . l/c including transportation loading and unloading etc.	64	Mtrs		
6.	Excavation of trenches of required width for laying of GI pipes, cables, poles etc., including dressing of sides, ramming of bottoms, suitable depth including getting out the excavated soil and the returning the soil including consolidating each deposit layer by ramming, watering etc., and disposing of surplus excavated soil as directed by engineer in charge and complete all labour and material 1. Soft/loose soil	150	M ³		
Total Rs.					

The Estimated coast is (put to tender) Rs.1,62,310/-

Criteria:

1. The firm has to pay cost of Tender Documents Rs.200/- in the form of B C / P O / D.D of any Nationalised Banks drawn in favour of F.A & C.A.O.
2. The firm has to pay has to pay E.M.D.Rs.3,246/- in the Demand Draft of any Nationalised Banks drawn in favour of F.A & C.A.O.
- 3.The firm has to submit the proof of experience in the similar field of work executed in other Govt departments/ports/PSUs or any other private organizations.

(The firms who are not complying with any one of the above criteria, their tender will be summarily Rejected.)

Terms and conditions:

The Contractor has to submit the offer duly super-scribing the name of the work on the envelope.

1. Firm's quoted rate shall be inclusive of all taxes & duties, except Service Tax.
2. Service Tax will be paid extra on submission of documentary evidence.
3. Validity of offer should be 01 month from the last date of receipt of the offers.
4. Statutory deductions will be made from the bills.
5. Conditional offers will be rejected.
6. In case of any clarification, Please contact at phone Nos: 2873193 / 2873207.
7. The workmanship and materials used in this work shall be guaranteed for a period of 06 months from the date of completion of the work.
8. The work should be completed within 10 days from the date of lifting the material / site clearance. The time for completion of the work is the essence of the contract.
9. The work shall be completed within the stipulated period, failing which a penalty @ ½% will be levied for every week of delay, on the part of the contractor subject to maximum 10% on total contract / executed value.

Sealed Quotations are to be addressed to:

Executive Engineer (Elec)
Mech & Electrical Engg.Dept.
Visakhapatnam Port Trust,
VISA KHAPATNAM-530035.

CONTRACTOR

EXECUTIVE ENGINEER(Elec)