

VISAKHAPATNAM PORT TRUST
MECHANICAL & ELECTRICAL ENGINEERING DEPARTMENT

TENDER NOTICE . No. /2018-19/IM&EE/MOF/FOF/ET/F.35 dt. 07 .06 . 2018

Sealed tenders are invited for the work :- Supply, Installation, retrofitting of panel mounted air conditioner- Capacity 500W, AC 230 V /50HZ for the use of Tugs Delima and Ried – Reg.

The Estimate cost (Put to Tender) Rs.3,59,161/-

Date of hoisting of Tender Documents: from 07- 06- 2018 at 16.30 hrs

Last date & time open of Tenders: 18-06-2017 at 15.00 Hrs.

Bid Validity; 60 Days.

1. The firm has to pay E.M.D Rs.7183/- (Rupees Seven thousand one hundred and eighty three only) in the form of Bankers' Cheque / pay order / Demand Draft of Nationalized / Scheduled Banks drawn in favour of F.A & C.A.O., VPT.
2. The firm has to pay cost of Tender Documents Rs.200/- in the form of B C / P O / D.D of any Nationalized / Scheduled Banks drawn in favour of F.A & C.A.O, VPT.
3. Only firm having experience in similar work i.e Supply, Installation, retrofitting of panel mounted air conditioner- Capacity 500W, AC 230 V /50HZ (doc to be submitted in support of experience).

SEALED COVER QUOTATIONS ARE TO BE ADDRESSED TO:

Superintending Engineer (E/T)
Mech & Electrical Engg.Dept
ADMINISTRATIVE OFFICE BUILDING
ROOM NO 204
Visakhapatnam Port Trust,
VISAKHAPATNAM-530035.

Enc; - Work Schedule.

SUPERINTENDENT ENGINEER(E/T)

CONTRACTOR

**VISAKHAPATNAM PORT TRUST
MECH. & ELEC. ENG. DEPARTMENT**

Sub: Supply, Installation, retrofitting of panel mounted air conditioner- Capacity
500W, AC 230 V /50HZ - Reg

WORK SCHEDULE

Sl. No	Description	Qty.	Rate Rs/-	Amount Rs/-
01	PANEL MOUNTED AIR CONDITIONER- CAPACITY 500W, AC 230 V /50HZ as per the specification at Annexure – A Make : Rittal , Advance Cooling System	04Nos		
02	GST Applicable			

Terms & conditions

1. Offer should be valid for 03 months period
2. All taxes should be clearly mentioned in the Offer.
3. Guarantee/Warranty period is 01 year
4. All taxes should be clearly mentioned in the tax column and GST certificate to be enclosed , IT @ 2% will be recovered by VPT.
6. No financial commitment at this stage on either side.
7. Firm has to submit proof of experience for similar work as prescribed
8. Specification of retrofitting of panel mounted air conditioner- Capacity 500W,
AC 230 V /50HZ and Accessories to be enclosed.

CONTRACTOR

SUPERINTENDENT ENGINEER (E/T)

Annexure –A

Sl. No	Specification	Description
01	Material	Sheet steel
02	Protection category IP to IEC 60 529	External Circuit IP 34 Internal Circuit IP 54
03	Rated operating Voltage:	230 V , 1 ,50 HZ /60 HZ
04	Dimensions	Width : 280 mm Height: 550 mm Depth : 210 mm
05	Temperature range	Operation (environment) : + 10 c..+ 55 C Setting Range : + 20 C. + 55 C
06	Air through (unimpeded air flow)	External Circuit : 315 m ³ /h Internal Circuit : 265 m ³ /h
07	Temperature Control	Comfort Controller (factory setting + 35 c)

CONTRACTOR

SUPERINTENDENT ENGINEER (E/T)