

VISAKHAPATNAM PORT TRUST
MECHANICAL & ELECTRICAL ENGG.DEPARTMENT

Name of work: Improvement of Lawn Lighting at Bungalow No.8 of Harbour Park –Reg
Last Date and Time of Receipt of Tenders in C.M.E.'s Office 05.10.2015 at 14.30 hours

ESTIMATE

S. No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Supply * Fixing of 1 x 18W CFL integral post top luminaire with conical shape, opal clear acrylic diffuser with cast aluminium pole mounting capsule complete with all accessories and lamp of reputed make as directed by engineer in-charge including all labour material tools and tackles makes Crompton / Bajaj / Surya / Havells / HPL.	35	Nos.		
2	Excavation of trenches of required width for laying of GI pipes, cables etc., including dressing of sides, ramming of bottoms, suitable depth including getting out the excavated soil and the returning the soil including consolidating each deposit layer by ramming, watering etc., and disposing of surplus excavated soil as directed by engineer in charge and complete all labour and material `` a) Soft/loose soil	125	M ³		
3	Laying / Clamping of 4 core, 10 Sqmm LT XLPE PVC insulated & PVC sheathed, armoured multi standard aluminium conductor Cable in the trench / to the pole with existing clamps complete as directed by engineer in charge including with all labour and material. (Cable will be supplied by VPT at Free of cost)	500	Mtrs		
4	Supply clamping of PVC conduit of size 1" on the existing wall / pole with clamps as directed by engineer in charge with all labour tools & tackles	100	Mtrs		
5	Supply & Drawing of 2 core, 1.1 KV grade, 1.5 Sq.mm, LT XLPE PVC insulated & PVC sheathed, armoured multi standard aluminium conductor Cable of approved brand and conforming to IS : 7098/II/85 through the existing pipe complete as directed by engineer in charge	100	Mtrs		

	including all labour, tools and tackles. Brands: GLOSTER/NICCO/FINECAB/HAVELLS/L&T / POLYCAB				
6	Supply and providing of P.C.C. 1:3:6 with 20 mm graded granite as coarse aggregate and river sand as fine aggregate (220 Kgs of cement per M ³ of finished concrete) including mixing, depositing in position, tamping, finishing and curing for base concreting, road cutting etc. as directed by engineer in charge including all labour and tools.	01	M ³		
7	Supply & laying /Clamping of 40 mm dia, medium grade G.I pipe to the wall/pole with existing clamps,/in the existing trench complete as directed by engineer in charge including all labour and material.	150	Mtrs		

EXECUTIVE ENGINEER (E/M)

Note: The Estimate cost is Rs.1,62,550/-

Criteria:

1.The firm has to pay E.M.D Rs.3,251/- in the form of Bankers' Cheque / Pay Order / Demand Draft of Nationalized Banks drawn in favour of F.A & C.A.O., VPT.

2.The firm has to pay cost of Tender Documents Rs.200/- in the form of B C / P O / D.D of any Nationalized Banks drawn in favour of F.A & C.A.O.

(The firms, who are not complying with any one of the above criteria, their tender will be summarily rejected)

Terms and conditions:

1. The Contractor has to submit the offer duly super-scribing the name of the work on the envelope.
2. Firm's quoted rate shall be inclusive of all taxes & duties but excluding Service Tax.
3. Validity of offer should be Three months from the last date of receipt of the offers.
4. Statutory deductions will be made from the bills.
5. Conditional offers will be rejected.
6. In case of any clarification, Please contact at phone No. 2873207/2873193.
7. The workmanship and materials used in this work shall be guaranteed for a period of Six months from the date of completion of the work.
8. The work should be completed within Thirty days from the date of lifting the material/ Site clearance. The time for completion of the work is the essence of the Contract.
9. The work shall be completed within the stipulated period, failing which a penalty @ ½% will be levied for every week of delay, on the part of the contractor subject to maximum 10% on total contract / executed value.

Sealed Quotations are to be addressed to:

Executive Engineer (Elec)
Mech & Electrical Engg.Dept.

Visakhapatnam Port Trust,
VISA KHAPATNAM-530035

CONTRACTOR

Executive Engineer (Elec)

VISAKHAPATNAM PORT TRUST
MECHANICAL & ELECTRICAL ENGG.DEPARTMENT

Name of work: Improvement of Lawn Lighting at Bungalow No.8 of Harbour Park –Reg

Last Date and Time of Receipt of Tenders in C.M.E.'s Office 05.10.2015 at 14.30 hours

ESTIMATE

S. No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Supply * Fixing of 1 x 18W CFL integral post top luminaire with conical shape, opal clear acrylic diffuser with cast aluminium pole mounting capsule complete with all accessories and lamp of reputed make as directed by engineer in-charge including all labour material tools and tackles makes Crompton / Bajaj / Surya / Havells / HPL.	35	Nos.		
2	Excavation of trenches of required width for laying of GI pipes, cables etc., including dressing of sides, ramming of bottoms, suitable depth including getting out the excavated soil and the returning the soil including consolidating each deposit layer by ramming, watering etc., and disposing of surplus excavated soil as directed by engineer in charge and complete all labour and material `` a) Soft/loose soil	125	M ³		
3	Laying / Clamping of 4 core, 10 Sqmm LT XLPE PVC insulated & PVC sheathed, armoured multi standard aluminium conductor Cable in the trench / to the pole with existing clamps complete as directed by engineer in charge including with all labour and material. (Cable will be supplied by VPT at Free of cost)	500	Mtrs		
4	Supply clamping of PVC conduit of size 1" on the existing wall / pole with clamps as directed by engineer in charge with all labour tools & tackles	100	Mtrs		

5	Supply & Drawing of 2 core, 1.1 KV grade, 1.5 Sq.mm, LT XLPE PVC insulated & PVC sheathed, armoured multi standard aluminium conductor Cable of approved brand and conforming to IS : 7098/II/85 through the existing pipe complete as directed by engineer in charge including all labour, tools and tackles. Brands: GLOSTER/NICCO/FINECAB/HAVELLS/L&T / POLYCAB	100	Mtrs		
6	Supply and providing of P.C.C. 1:3:6 with 20 mm graded granite as coarse aggregate and river sand as fine aggregate (220 Kgs of cement per M ³ of finished concrete) including mixing, depositing in position, tamping, finishing and curing for base concreting, road cutting etc. as directed by engineer in charge including all labour and tools.	01	M ³		
7	Supply & laying /Clamping of 40 mm dia, medium grade G.I pipe to the wall/pole with existing clamps,/in the existing trench complete as directed by engineer in charge including all labour and material.	150	Mtrs		

EXECUTIVE ENGINEER (E/M)

Note: The Estimate cost is Rs.1,62,550/-

Criteria:

1.The firm has to pay E.M.D Rs.3,251/- in the form of Bankers' Cheque / Pay Order / Demand Draft of Nationalized Banks drawn in favour of F.A & C.A.O., VPT.

2.The firm has to pay cost of Tender Documents Rs.200/- in the form of B C / P O / D.D of any Nationalized Banks drawn in favour of F.A & C.A.O.

(The firms, who are not complying with any one of the above criteria, their tender will be summarily rejected)

Terms and conditions:

1. The Contractor has to submit the offer duly super-scribing the name of the work on the envelope.
2. Firm's quoted rate shall be inclusive of all taxes & duties but excluding Service Tax.
3. Validity of offer should be Three months from the last date of receipt of the offers.
4. Statutory deductions will be made from the bills.
5. Conditional offers will be rejected.
6. In case of any clarification, Please contact at phone No. 2873207/2873193.
7. The workmanship and materials used in this work shall be guaranteed for a period of Six months from the date of completion of the work.
8. The work should be completed within Thirty days from the date of lifting the material/ Site clearance. The time for completion of the work is the essence of the Contract.
9. The work shall be completed within the stipulated period, failing which a penalty @ ½% will be levied for every week of delay, on the part of the contractor subject to maximum 10% on total contract / executed value.

Sealed Quotations are to be addressed to:

Executive Engineer (Elec)
Mech & Electrical Engg.Dept.

Visakhapatnam Port Trust,
VISA KHAPATNAM-530035

CONTRACTOR

Executive Engineer (Elec)

