

VISAKHAPATNAM PORT TRUST
MECHANICAL & ELECTRICAL ENGINEERING DEPARTMENT

TENDER NOTICE . No. 49/2016-17/IM&EE/MOF/FOF/ET/F.06 / .04.04.2016

Sealed tenders are invited for the work :- Replacement and Re-programming of CPU (s7-300 PLC) in VPT Pollution control vessel-Jalsudhak – Reg.

The Estimate cost (Put to Tender) Rs.94,875/-

Date of hoisting of Tender Documents: from 05.04.2016 at 16.30 hrs. to 20.04.2016 at 14.00 hrs.

Last date & time open of Tenders: 21-04-2016 at 14.00 Hrs.

Bid Validity: 30 Days.

1. The firm has to pay E.M.D Rs.1898/- (Rupees one thousand eight hundred and ninety eight only) in the form of Bankers' Cheque / pay order / Demand Draft of Nationalized / Scheduled Banks drawn in favour of F.A & C.A.O., VPT.
2. The firm has to pay cost of Tender Documents Rs.200/- in the form of B C / P O / D.D of any Nationalized / Scheduled Banks drawn in favour of F.A & C.A.O, VPT.

Sealed Cover Quotations are to be addressed to:

Superintending Engineer (E/T)
Mech & Electrical Engg.Dept
ADMINISTRATIVE OFFICE BUILDING
ROOM NO 204
Visakhapatnam Port Trust,
VISAKHAPATNAM-530035.

Enc;:- Work Schedule.

DY.CHIEF MECHANICAL ENGINEER

VISAKHAPATNAM PORT TRUST
MECHANICAL ENGINEERING DEPARTMENT

Sub: Replacement of CPU,(S7-300 PLC) in Pollution Launch Jalsudhak in VPT

VPT Garbage launch is fitted with M/S Seimens PLC controls (S7-300) for crane controls (open,close, door open ,close etc). it is proposed to replace defective CPU and HMI with new modules and re-programme ,re-commission garbage launch to its normal operations.

WORK SCHEDULE

Sl No	Item description	Qty	Unit price	Total Amount
01	Replacement of CPU with 16 ch I/Os for crane controls consists of a)CPU-226CN AC/DC/RLY Model: S7 200 CN Make : SEIMENS	01 set		
02	Re-Programming and Re-commissioning charges for normal crane and door operations	Lumpsum		
	Total In Rupees			

Terms& conditions:

- a) Offer should be valid for 02 months.
- b) All applicable taxes to clearly mentioned.
- c) Warranty 01 year from the date of completion.
- d) Technical details/product details/catalogue to be furnished for quoted product.
- e) Work should be completed within 2 weeks from date of issuing site clearance by VPT.
- f) Material supply at VPT site only.
- g)** Reprogramming of crane controls (Boom Reel, Ban door open, close skimmer on (off, debris door open/close are as per VPT vessel operations requirement. Hence bidder to study vessel crane controls and prior submission)