

VISAKHAPATNAM PORT TRUST  
MECHANICAL & ELECTRICAL ENGINEERING DEPARTMENT

**TENDER NOTICE . No. /2018-19/IM&EE/MOF/FOF/ET/F.35 dt. 22 .06 . 2018**

Sealed tenders are invited for the work :- Supply, Installation, retrofitting of panel mounted air conditioner- Capacity 500W, AC 230 V /50HZ for the use of Tugs Delima and Ried – Reg.

The Estimate cost (Put to Tender) Rs.3,59,161/-

Date of hoisting of Tender Documents: from 22- 06- 2018 at 16.30 hrs

Last date & time open of Tenders: 30-06-2018 at 15.00 Hrs.

Bid Validity: 60 Days.

1. The firm has to pay E.M.D Rs.7183/- (Rupees Seven thousand one hundred and eighty three only) in the form of Bankers' Cheque / pay order / Demand Draft of Nationalized / Scheduled Banks drawn in favour of F.A & C.A.O., VPT.
2. The firm has to pay cost of Tender Documents Rs.200/- in the form of B C / P O / D.D of any Nationalized / Scheduled Banks drawn in favour of F.A & C.A.O, VPT.
3. Only firm having experience in similar work i.e Supply, Installation, retrofitting of panel mounted air conditioner- Capacity 500W, AC 230 V /50HZ ( doc to be submitted in support of experience ).

**SEALED COVER QUOTATIONS ARE TO BE ADDRESSED TO:**

Superintending Engineer (E/T)  
Mech & Electrical Engg.Dept  
ADMINISTRATIVE OFFICE BUILDING  
ROOM NO 204  
Visakhapatnam Port Trust,  
VISAKHAPATNAM-530035.

**SUPERINTENDENT ENGINEER(E/T)**

Enc; - Work Schedule.

**VISAKHAPATNAM PORT TRUST  
MECH. & ELEC. ENG. DEPARTMENT**

Sub: Supply, Installation, retrofitting of panel mounted air conditioner- Capacity  
500W, AC 230 V /50HZ - Reg

**WORK SCHEDULE**

<b>Sl. No</b>	<b>Description</b>	<b>Qty.</b>	<b>Rate Rs/-</b>	<b>Amount Rs/-</b>
01	PANEL MOUNTED AIR CONDITIONER- CAPACITY 500W, AC 230 V /50HZ as per the specification at Annexure – A Make : Rittal , Advance Cooling System	04Nos		
02	GST Applicable			

**Terms & conditions**

1. Offer should be valid for 03 months period
2. All taxes should be clearly mentioned in the Offer.
3. Guarantee/Warantee period is 01 year
4. All taxes should be clearly mentioned in the tax column and GST certificate to be enclosed , IT @ 2% will be recovered by VPT.
6. No financial commitment at this stage on either side.
7. Firm has to submit proof of experience for similar work as prescribed
8. Specification of retrofitting of panel mounted air conditioner- Capacity 500W,  
AC 230 V /50HZ and Accessories to be enclosed.

**CONTRACTOR**

**SUPERINTENDENT ENGINEER (E/T)**

## Annexure -A

Sl. No	Specification	Description
01	Material	Sheet steel
02	Protection category IP to IEC 60 529	External Circuit IP 34 Internal Circuit IP 54
03	Rated operating Voltage:	230 V , 1 ,50 HZ /60 HZ
04	Dimensions	Width : 280 mm Height: 550 mm Depth : 210 mm
05	Temperature range	Operation ( environment ) : + 10 c..+ 55 C Setting Range : + 20 C. + 55 C
06	Air through ( unimpeded air flow )	External Circuit : 315 m <sup>3</sup> /h Internal Circuit : 265 m <sup>3</sup> /h
07	Temperature Control	Comfort Controller ( factory setting + 35 c )

**CONTRACTOR**

**SUPERINTENDENT ENGINEER (E/T)**