



VISAKHAPATNAM PORT TRUST
Mechanical & Electrical Engineering Department

No.IM&EE/MOF/Elec/F.1106
Dt.29.01.2015

Sealed tenders are invited (**2nd Call**) for the work of “Replacement of existing corroded / damaged street lighting poles at various locations / roads in port area i.e., Elephant gate road, STP road, North cabin road etc”. The schedule of work is furnished below:

Last date & time of Receipt of Tenders in CME’s office:21.02.2015 at 15.00 Hrs

WORK SCHEDULE

Sl. No	Description	Qty	Unit	Rate Rs. Ps.	Amount Rs. Ps.
1	Excavation of pit/trench of required width and depth for laying of HT/LT cable/pipe, erection of pole/strut, earth pit/stay set etc., refilling and making the surface good to match the surroundings including removal of debris complete as directed by Engineer in charge with all labour and tools. a) Hard / dense soil b) Soft / loose soil	10 20	M ³ M ³		
2	Supply and providing of P.C.C. 1:3:6 with 20 mm graded granite as coarse aggregate and river sand as fine aggregate (220 Kgs of cement per M ³ of finished concrete) including mixing, depositing in position, tamping, finishing and curing for base concreting, road cutting pole coping, footing for panels etc. as directed by Engineer in charge including all labour and tools.	28	M ³		
3	Supply and fabrication of steel by using suitable flats, angles, channels of required sizes to provide required cross arms, back clamps, formation of 4 Pole structures, for fixing of HT/LT pin/disc/shackle insulators, lightning arrestors, H.G Fuse sets, A.B. Switches including cutting, bolting, riveting, drilling, welding etc. including providing one coat of zinc rich epoxy paint primer complete as directed by Engineer in charge.	200	Kg		
4	Transportation, placement, erection of 11/13 meters long S.H B.G rails Poles duly supply and welded with a base plate of size 300X300X10 mm, in the existing trench for poles /struts with all material, labour and tools as directed by Engineer-in-charge. (S.H.B.G. Rail poles will be supplied by VPT at free of cost)	15	No		

CONTRACTOR

Executive Engineer (Elec)

5	Removal of existing B.G. rail pole duly breaking the coping and base PCC, excavating the earth unto 0.5mts depth from the ground level cutting the pole refilling the excavated earth and making the surface good to match the surroundings, returning the removed pole to E/M section stores /general stores as directed by Engineer in charge including all labour, tools, tackles, and transportation, loading and unloading.	10	No		
				Total - - - - Rs.	

Note:

The Estimate cost is Rs.1,72,263/-

Criteria:

1. The firm has to pay E.M.D Rs.3,445/- in the form of Bankers' Cheque / pay order / Demand Draft of Nationalised Banks drawn in favour of F.A & C.A.O., VPT.
2. The firm has to pay cost of Tender Documents Rs.200/- in the form of B C / P O / D.D of any Nationalised Banks drawn in favour of F.A & C.A.O.

(The firms who are not complying with any one of the above criteria, their tender will be summarily rejected)

Terms and conditions:

1. The Contractor has to submit the offer duly super-scribing the name of the work on the envelope.
2. Firm's quoted rate shall be inclusive of all taxes & duties, except Service Tax.
3. Service Tax will be paid extra on submission of documentary evidence.
4. Validity of offer should be 01 month from the last date of receipt of the offers.
5. Statutory deductions will be made from the bills.
6. Conditional offers will be rejected.
7. In case of any clarification, Please contact at phone Nos: 2873193 / 2873207.
8. The workmanship and materials used in this work shall be guaranteed for a period of 12 months from the date of completion of the work.
9. The work should be completed within 21 days from the date of lifting the material / site clearance. The time for completion of the work is the essence of the contract.
10. The work shall be completed within the stipulated period, failing which a penalty @ ½% will be levied for every week of delay, on the part of the contractor subject to maximum 10% on total contract / executed value.
11. The tenderers can visit VPT Website www.vizagport.com to download tender documents.

Sealed Quotations are to be addressed to:

Supdt. Engineer (Elec)
Mech & Electrical Engg.Dept.
Visakhapatnam Port Trust,
VISA KHAPATNAM-530035.

CONTRACTOR

Executive Engineer (Elec)